



NOTES:

1. CONTRACTOR MAY OMIT TRANSVERSE #3 REBAR IF PLACING CURB AND GUTTER MONOLITHICALLY.
2. REINFORCED CONCRETE SHALL BE MINIMUM 3,600 PSI @ 28 DAYS



**CITY OF
DECATUR**

**PAVING CONSTRUCTION DETAILS
STANDARD CURB AND GUTTER**

REVISED OCT 2001

SCALE: 1/2" = 1'

SHEET: **P-4**